



GOVERNMENT OF PAKISTAN
PAKISTAN PUBLIC WORKS DEPARTMENT
PAK. P.W.D. OFFICE BLOCK, 16-CANTT. STATION ROAD,
ADJACENT CANTT. POST OFFICE, SADDAR, KARACHI-75530
PH # 99332066

No. EE.CCD-VI/AB/NIT/4038

Karachi dated: 13th March 2024.

INVITATION TO BID

The Executive Engineer, Central Civil Division No. VI, Pak PWD, Karachi, invites sealed tenders, under Single Stage Two Envelope & on percentage rate basis for the work tabulated hereunder, from the Contractors/Firms registered with Income Tax, Sindh Revenue Board & having valid licence of Pakistan Engineering Council in appropriate category & field of specializations.

2. A complete set of Bidding Documents containing detailed terms and conditions may be purchased by an interested eligible bidder upon payment of a non-refundable fee as shown against each in cash.
3. Bidders will submit two sealed envelopes simultaneously, one containing the Technical Proposal and the other Financial Proposals, duly marked separately and enclosed together in an outer single envelope, in consonance with Rule-36(b) of PPRA 2004, so as to reach the undersigned. Technical proposals will be opened on the same day in the presence of bidders/ representatives who choose to attend, at the same address. The time and schedule are narrated hereunder:
 - i. Issuance of Bidding documents up to: 01-04-2024 (office Hours).
 - ii. Casting / dropping of Bids up to: 02-04-2024. 11:00 A.M.
 - iii. Opening of Technical Bids on: 02-04-2024. 11:30 A.M.
4. In accordance with PPRA Rule-25; Bid Security i.e fixed amount as mentioned against each work is required, in shape of **CDR/Pay order/Bank Draft/Bank Guarantee** by any schedule bank in favor of undersigned. The bidder will submit /attached original bid Security along with Technical Proposal; otherwise it will be treated NON-RESPONSIVE.

S. No.	Name of Schemes	Amount (Million)	Bid Security /Earnest Money	Tender Cost
1	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Arslan Homes, Shah Nawaz Bhutto Colony in UC-01, District Central North Karachi.	13.713	411,400	2,000
2	Providing and Fixing CC Tuff paver at Different streets of Sector-2 in UC-01, District Central North Karachi.	9.766	293,000	2,000
3	Providing and Fixing CC Tuff paver at Different streets of Sector-3 in UC-01, District Central North Karachi.	9.766	293,000	2,000
4	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector 5A-1&2 in UC-02, District Central North Karachi.	13.713	411,400	2,000
5	Providing and Fixing CC Tuff paver at Different streets of 5B1&2 in UC-02, District Central North Karachi.	9.766	293,000	2,000
6	Providing and Fixing CC Tuff paver at Different streets of 5A3&4 in UC-02, District Central North Karachi.	9.766	293,000	2,000
7	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5B3 & 5C1 UC-03, District Central North Karachi.	13.713	411,400	2,000
8	Providing and Fixing CC Tuff paver at Different streets of Sector-5C2 in UC-03, District Central North Karachi.	9.766	293,000	2,000
9	Providing and Fixing CC Tuff paver at Different streets of Sector-4 in UC-03, District Central North Karachi.	9.766	293,000	2,000
10	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector 5M & 5I in UC-04, District Central North Karachi.	13.713	411,400	2,000
11	Providing and Fixing CC Tuff paver at Different streets of Sector 5M in UC-04, District Central North Karachi.	9.766	293,000	2,000
12	Providing and Fixing CC Tuff paver at Different streets of Sector 5M & 5I in UC-04, District Central North Karachi.	9.766	293,000	2,000
13	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5L & 5K in UC-08, District Central North Karachi.	13.713	411,400	2,000

14	Providing and Fixing CC Tuff paver at Different streets of Sector-5L in UC-08,District Central North Karachi.	9.766	293,000	2,000
15	Providing and Fixing CC Tuff paver at Different streets of Sector- 5K in UC-08,District Central North Karachi.	9.766	293,000	2,000
16	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-11L,11I & 11K in UC-11,District Central North Karachi.	13.713	411,400	2,000
17	Providing and Fixing CC Tuff paver at Different streets of Sector-11L & 11I in UC-11,District Central North Karachi.	9.766	293,000	2,000
18	Providing and Fixing CC Tuff paver at Different streets of Sector-11I & 11K in UC-11,District Central North Karachi.	9.766	293,000	2,000
19	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5C3 & 5C4 in UC-12,District Central North Karachi.	13.713	411,400	2,000
20	Providing and Fixing CC Tuff paver at Different streets of Sector-11A in UC-12,District Central North Karachi.	9.766	293,000	2,000
21	Providing and Fixing CC Tuff paver at Different streets of Sector- 11B in UC-12,District Central North Karachi.	9.766	293,000	2,000
22	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-8 & 9 in UC-13,District Central North Karachi.	13.713	411,400	2,000

Terms & Conditions:

6. No bidding document will be issued on the day of opening & no application will be entertained for issuance after cutoff date as mentioned at para 3(i), which will strictly be adhered to. The competent authority in accordance with PPRA Rules-33 of 2004 may reject all bids/proposals any time prior to the acceptance of a bid/proposal. Other terms and conditions as envisaged in the bidding documents will apply mutatis mutandis.

---Sd---
(IMRAN SHAMS)
Executive Engineer
Central Civil Div. No. VI,
Pak. P.W.D. Karachi.

**Name of Work:Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at
Different streets of Arslan Homes,Shah Nawaz Bhutto Colony in UC-01,District
Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver
SH-II SEWERAGE LINE

Rs. 8,624,400
1,616,768
Rs. 10,241,168

TOTAL

Name of Work:Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Arslan Homes,Shah Nawaz Bhutto Colony in UC-01,District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	35000	Sft	332.5	%sft	116,375
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour patten (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	35000	sft	135.13	P.sft	4,729,550
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	11550	cft	27877.27	% cft	3,219,825
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	50	Nos	11,173.00	P.No	558,650

TOTAL Rs. 8,624,400

SH-II SEWERAGE LINE							
1	313/05	Excavation in all kinds of soil, murum, hard, average or soft including all lift and lead .	15284	cft	1840.9	%cft	281,365
2	313/05 +15upto 8 feet	9170	cft	2078.4	%cft	190,599
3	312/07	Providing R.C.C pipes and collars of class 'B' and fixing in trench i/c cutting ,fitting and jointing with maxphalt composition and cement mortar (1:1) and back filling the excaforvated material in trench i/c testing with water to a pressure head of 50 feet (15.24m) and cartage within 10 miles (16.09 km),for 12 inches (305mm) dia,pipe	1000	Rft	548.16	P.Rft	548,160

4	A/R	Providing circular manhole comprised of cylindrical and conical portions as per approved design and specifications complete with RCC 1:2:4 slab, 6 inches thick c.c. 1:3:6 Situ walls 9 inches thick with deduction of pipe holes CC 1:3:6 in foundation 6 inches thick and 1:2:4 CC in benching using sulphate resisting cement in all cc works including providing and fixing cost iron foot rest at every two feet of depth completed as per direction of engineer incharge but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	1000	cft	545.9	P.cft	545,900
5		Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	20	cft	2274.73	P.cft	45,495
6		Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc.complete.	7	Nos	750.00	P.NO	5,250
					TOTAL Rs.		1,616,768

#REF!

TOTAL Rs.	7,293,382
------------------	------------------

TOTAL Rs.	7,293,382
------------------	------------------

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-3 in UC-01, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-3 in UC-01, District Central North Karachi.

S.No		Item of work	Qty		Rate	Unit	Amount
		SH-I Providing and Laying CC Tuff Paver					
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	30000	Sft	332.5	%sft	99,750
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	30000	sft	135.13	P.sft	4,053,900
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	9900	cft	27877.27	% cft	2,759,850
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	34	Nos	11,173.00	P.No	379,882

TOTAL Rs.	7,293,382
------------------	------------------

**Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at
Different streets of Sector 5A-1&2 in UC-02, District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver
SH-II SEWERAGE LINE

Rs. 8,624,400
1,616,768
Rs. 10,241,168

TOTAL

Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector 5A-1&2 in UC-02, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	35000	Sft	332.5	%sft	116,375
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	35000	sft	135.13	P.sft	4,729,550
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	11550	cft	27877.27	% cft	3,219,825
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	50	Nos	11,173.00	P.No	558,650

TOTAL Rs. 8,624,400

SH-II SEWERAGE LINE							
1	313/05	Excavation in all kinds of soil, murum, hard, average or soft including all lift and lead .	15284	cft	1840.9	%cft	281,365
2	313/05 +15upto 8 feet	9170	cft	2078.4	%cft	190,599
3	312/07	Providing R.C.C pipes and collars of class 'B' and fixing in trench i/c cutting ,fitting and jointing with maxphalt composition and cement mortar (1:1) and back filling the excaforvated material in trench i/c testing with water to a pressure head of 50 feet (15.24m) and cartage within 10 miles (16.09 km),for 12 inches (305mm) dia,pipe	1000	Rft	548.16	P.Rft	548,160

4	A/R	Providing circular manhole comprised of cylindrical and conical portions as per approved design and specifications complete with RCC 1:2:4 slab, 6 inches thick c.c. 1:3:6 Situ walls 9 inches thick with deduction of pipe holes CC 1:3:6 in foundation 6 inches thick and 1:2:4 CC in benching using sulphate resisting cement in all cc works including providing and fixing cast iron foot rest at every two feet of depth completed as per direction of engineer incharge but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	1000	cft	545.9	P.cft	545,900
5		Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	20	cft	2274.73	P.cft	45,495
6		Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc.complete.	7	Nos	750.00	P.NO	5,250
					TOTAL Rs.		1,616,768

Name of Work:Providing and Fixing CC Tuff paver at Different streets of 5B1&2 in UC-02,District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of 5B1&2 in UC-02, District Central North Karachi.

[illegible]

Name of Work:Providing and Fixing CC Tuff paver at Different streets of 5A3&4 in UC-02,District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work:Providing and Fixing CC Tuff paver at Different streets of 5A3&4 in UC-02,District Central North Karachi.

[illegible]

TOTAL Rs.	7,293,382
-----------	-----------

**Name of Work:Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at
Different streets of Sector-5B3 & 5C1 UC-03,District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver
SH-II SEWERAGE LINE

Rs. 8,624,400
1,616,768

Rs. 10,241,168

TOTAL

Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5B3 & 5C1 UC-03, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	35000	Sft	332.5	%sft	116,375
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	35000	sft	135.13	P.sft	4,729,550
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	11550	cft	27877.27	% cft	3,219,825
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	50	Nos	11,173.00	P.No	558,650

TOTAL Rs. 8,624,400

SH-II SEWERAGE LINE							
1	313/05	Excavation in all kinds of soil, murum, hard, average or soft including all lift and lead .	15284	cft	1840.9	%cft	281,365
2	313/05 +15upto 8 feet	9170	cft	2078.4	%cft	190,599
3	312/07	Providing R.C.C pipes and collars of class 'B' and fixing in trench i/c cutting ,fitting and jointing with maxphalt composition and cement mortar (1:1) and back filling the excaforvated material in trench i/c testing with water to a pressure head of 50 feet (15.24m) and cartage within 10 miles (16.09 km),for 12 inches (305mm) dia,pipe	1000	Rft	548.16	P.Rft	548,160

4	A/R	Providing circular manhole comprised of cylindrical and conical portions as per approved design and specifications complete with RCC 1:2:4 slab, 6 inches thick c.c. 1:3:6 Situ walls 9 inches thick with deduction of pipe holes CC 1:3:6 in foundation 6 inches thick and 1:2:4 CC in benching used sulphate resisting cement in all cc works including providing and fixing cast iron foot rest at every two feet of depth completed as per direction of engineer incharge but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	1000	cft	545.9	P.cft	545,900
5		Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	20	cft	2274.73	P.cft	45,495
6		Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc.complete.	7	Nos	750.00	P.NO	5,250
					TOTAL Rs.		1,616,768

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-5C2 in UC-03, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-5C2 in UC-03, District Central North Karachi.

[illegible]

**Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-4
in UC-03, District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382

Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-4 in UC-03, District Central North Karachi.

[illegible]

**Name of Work:Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at
Different streets of Sector 5M & 5I in UC-04,District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver		Rs. 8,624,400
SH-II SEWERAGE LINE		1,616,768
	TOTAL	Rs. 10,241,168

Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector 5M & 5I in UC-04, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	35000	Sft	332.5	%sft	116,375
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	35000	sft	135.13	P.sft	4,729,550
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	11550	cft	27877.27	% cft	3,219,825
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	50	Nos	11,173.00	P.No	558,650

TOTAL Rs. 8,624,400

SH-II SEWERAGE LINE							
1	313/05	Excavation in all kinds of soil, murum, hard, average or soft including all lift and lead .	15284	cft	1840.9	%cft	281,365
2	313/05 +15upto 8 feet	9170	cft	2078.4	%cft	190,599
3	312/07	Providing R.C.C pipes and collars of class 'B' and fixing in trench i/c cutting ,fitting and jointing with maxphalt composition and cement mortar (1:1) and back filling the excaforvated material in trench i/c testing with water to a pressure head of 50 feet (15.24m) and cartage within 10 miles (16.09 km),for 12 inches (305mm) dia,pipe	1000	Rft	548.16	P.Rft	548,160

4	A/R	Providing circular manhole comprised of cylindrical and conical portions as per approved design and specifications complete with RCC 1:2:4 slab, 6 inches thick c.c. 1:3:6 Situ walls 9 inches thick with deduction of pipe holes CC 1:3:6 in foundation 6 inches thick and 1:2:4 CC in benching used sulphate resisting cement in all cc works including providing and fixing cast iron foot rest at every two feet of depth completed as per direction of engineer incharge but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	1000	cft	545.9	P.cft	545,900
5		Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	20	cft	2274.73	P.cft	45,495
6		Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc.complete.	7	Nos	750.00	P.NO	5,250
					TOTAL Rs.		1,616,768

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector 5M in UC-04, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work:Providing and Fixing CC Tuff paver at Different streets of Sector 5M in UC-04,District Central North Karachi.

[illegible]

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector 5M & 5I in UC-04, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector 5M & 5I in UC-04, District Central North Karachi.

[illegible]

**Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at
Different streets of Sector-5L & 5K in UC-08, District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver
SH-II SEWERAGE LINE

Rs. 8,624,400
1,616,768
Rs. 10,241,168

TOTAL

Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5L & 5K in UC-08, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	35000	Sft	332.5	%sft	116,375
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	35000	sft	135.13	P.sft	4,729,550
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	11550	cft	27877.27	% cft	3,219,825
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	50	Nos	11,173.00	P.No	558,650

TOTAL Rs. 8,624,400

SH-II SEWERAGE LINE							
1	313/05	Excavation in all kinds of soil, murum, hard, average or soft including all lift and lead .	15284	cft	1840.9	%cft	281,365
2	313/05 +15upto 8 feet	9170	cft	2078.4	%cft	190,599
3	312/07	Providing R.C.C pipes and collars of class 'B' and fixing in trench i/c cutting ,fitting and jointing with maxphalt composition and cement mortar (1:1) and back filling the excaforvated material in trench i/c testing with water to a pressure head of 50 feet (15.24m) and cartage within 10 miles (16.09 km),for 12 inches (305mm) dia,pipe	1000	Rft	548.16	P.Rft	548,160

4	A/R	Providing circular manhole comprised of cylindrical and conical portions as per approved design and specifications complete with RCC 1:2:4 slab, 6 inches thick c.c. 1:3:6 Situ walls 9 inches thick with deduction of pipe holes CC 1:3:6 in foundation 6 inches thick and 1:2:4 CC in benching using sulphate resisting cement in all cc works including providing and fixing cast iron foot rest at every two feet of depth completed as per direction of engineer incharge but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	1000	cft	545.9	P.cft	545,900
5		Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	20	cft	2274.73	P.cft	45,495
6		Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc.complete.	7	Nos	750.00	P.NO	5,250
					TOTAL Rs.		1,616,768

**Name of Work:Providing and Fixing CC Tuff paver at Different streets of Sector-5L
in UC-08,District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

<p>Name of Work:Providing and Fixing CC Tuff paver at Different streets of Sector-5L in UC-08,District Central North Karachi.</p>
--

S.No		item of work	Qty		Rate	Unit	Amount
		SH-I Providing and Laying CC Tuff Paver					
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	30000	Sft	332.5	%sft	99,750
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour patten (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	30000	sft	135.13	P.sft	4,053,900
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	9900	cft	27877.27	% cft	2,759,850
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	34	Nos	11,173.00	P.No	379,882

TOTAL Rs.	7,293,382
-----------	-----------

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-5K in UC-08, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-5K in UC-08, District Central North Karachi.

[illegible]

**Name of Work:Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at
Different streets of Sector-11L,11I & 11K in UC-11,District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver
SH-II SEWERAGE LINE

Rs. 8,624,400
1,616,768

Rs. 10,241,168

TOTAL

Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-11L, 11I & 11K in UC-11, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	35000	Sft	332.5	%sft	116,375
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	35000	sft	135.13	P.sft	4,729,550
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	11550	cft	27877.27	% cft	3,219,825
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	50	Nos	11,173.00	P.No	558,650

TOTAL Rs. 8,624,400

SH-II SEWERAGE LINE							
1	313/05	Excavation in all kinds of soil, murum, hard, average or soft including all lift and lead .	15284	cft	1840.9	%cft	281,365
2	313/05 +15upto 8 feet	9170	cft	2078.4	%cft	190,599
3	312/07	Providing R.C.C pipes and collars of class 'B' and fixing in trench i/c cutting ,fitting and jointing with maxphalt composition and cement mortar (1:1) and back filling the excaforvated material in trench i/c testing with water to a pressure head of 50 feet (15.24m) and cartage within 10 miles (16.09 km),for 12 inches (305mm) dia,pipe	1000	Rft	548.16	P.Rft	548,160

4	A/R	Providing circular manhole comprised of cylindrical and conical portions as per approved design and specifications complete with RCC 1:2:4 slab, 6 inches thick c.c. 1:3:6 Situ walls 9 inches thick with deduction of pipe holes CC 1:3:6 in foundation 6 inches thick and 1:2:4 CC in benching using sulphate resisting cement in all cc works including providing and fixing cast iron foot rest at every two feet of depth completed as per direction of engineer incharge but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	1000	cft	545.9	P.cft	545,900
5		Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	20	cft	2274.73	P.cft	45,495
6		Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc.complete.	7	Nos	750.00	P.NO	5,250
					TOTAL Rs.		1,616,768

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-11L & 11I in UC-11, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-11L & 11I in UC-11, District Central North Karachi.

[illegible]

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-11I & 11K in UC-11, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-11I & 11K in UC-11, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	30000	Sft	332.5	%sft	99,750
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	30000	sft	135.13	P.sft	4,053,900
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	9900	cft	27877.27	% cft	2,759,850
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	34	Nos	11,173.00	P.No	379,882
TOTAL Rs.							7,293,382

**Executive Engineer
Central Civil Division No-VI
Pak.PWD Karachi**

**Name of Work:Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at
Different streets of Sector-5C3 & 5C4 in UC-12,District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver
SH-II SEWERAGE LINE

Rs. 8,624,400
1,616,768

Rs. 10,241,168

TOTAL

Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5C3 & 5C4 in UC-12, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	35000	Sft	332.5	%sft	116,375
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	35000	sft	135.13	P.sft	4,729,550
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	11550	cft	27877.27	% cft	3,219,825
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	50	Nos	11,173.00	P.No	558,650

TOTAL Rs. 8,624,400

SH-II SEWERAGE LINE							
1	313/05	Excavation in all kinds of soil, murum, hard, average or soft including all lift and lead .	15284	cft	1840.9	%cft	281,365
2	313/05 +15upto 8 feet	9170	cft	2078.4	%cft	190,599
3	312/07	Providing R.C.C pipes and collars of class 'B' and fixing in trench i/c cutting ,fitting and jointing with maxphalt composition and cement mortar (1:1) and back filling the excaforvated material in trench i/c testing with water to a pressure head of 50 feet (15.24m) and cartage within 10 miles (16.09 km),for 12 inches (305mm) dia,pipe	1000	Rft	548.16	P.Rft	548,160

4	A/R	Providing circular manhole comprised of cylindrical and conical portions as per approved design and specifications complete with RCC 1:2:4 slab, 6 inches thick c.c. 1:3:6 Situ walls 9 inches thick with deduction of pipe holes CC 1:3:6 in foundation 6 inches thick and 1:2:4 CC in benching using sulphate resisting cement in all cc works including providing and fixing cast iron foot rest at every two feet of depth completed as per direction of engineer incharge but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	1000	cft	545.9	P.cft	545,900
5		Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	20	cft	2274.73	P.cft	45,495
6		Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc.complete.	7	Nos	750.00	P.NO	5,250
					TOTAL Rs.		1,616,768

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-11A in UC-12, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

<p>Name of Work:Providing and Fixing CC Tuff paver at Different streets of Sector-11A in UC-12,District Central North Karachi.</p>

S.No		item of work	Qty		Rate	Unit	Amount
		SH-I Providing and Laying CC Tuff Paver					
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	30000	Sft	332.5	%sft	99,750
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	30000	sft	135.13	P.sft	4,053,900
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	9900	cft	27877.27	% cft	2,759,850
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	34	Nos	11,173.00	P.No	379,882
						TOTAL Rs.	7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-11B in UC-12, District Central North Karachi.

ABSTRACT OF COST

SH-ICC Tuff Paver

TOTAL

Rs. 7,293,382
Rs. 7,293,382

Name of Work: Providing and Fixing CC Tuff paver at Different streets of Sector-11B in UC-12, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
		SH-I Providing and Laying CC Tuff Paver					
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	30000	Sft	332.5	%sft	99,750
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	30000	sft	135.13	P.sft	4,053,900
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	9900	cft	27877.27	% cft	2,759,850
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	34	Nos	11,173.00	P.No	379,882
TOTAL Rs.							7,293,382

**Executive Engineer
Central Civil Division No-VI
Pak.PWD Karachi**

**Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at
Different streets of Sector-8 & 9 in UC-13, District Central North Karachi.**

ABSTRACT OF COST

SH-ICC Tuff Paver
SH-II SEWERAGE LINE

Rs. 8,624,400
1,616,768
Rs. 10,241,168

TOTAL

Name of Work: Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-8 & 9 in UC-13, District Central North Karachi.

S.No		item of work	Qty		Rate	Unit	Amount
SH-I Providing and Laying CC Tuff Paver							
1	S/R	Levelling and dressing the ground by cutting and filling earth upto 6 inches (152 mm) in depth including consolidating and watering, complete as required.	35000	Sft	332.5	%sft	116,375
2	117/15 7 P 208	Providing and laying in floor C.C. 1:2:4: tuff paver 2-1/2" thick of approved design and colour pattern (average strength 7000 psi) laid on sand cushion filling of joint with sand and warring etc. complete as per direction of Engineer Incharge. (the cost of sand cushion is included)	35000	sft	135.13	P.sft	4,729,550
3	127/94	Providing and laying 1:4:8 cement concrete in any thickness using 2" (51 mm) and down gauge stone ballast of approved grade and quality over prepared sub-grade or sand cushion in roads, paths, creteways laid to required gradient and camber including cost of necessary form work and its removal compacting with vibrators including curing etc. complete .	11550	cft	27877.27	% cft	3,219,825
4		Providing and laying RCC Circular top slab (5 inch thick 3feet outer dia) for man hole, using crush graded boulder 3/4" and down gauge having a minimum works cube crushing strength 3000 PSI at 29 days with a mix nt leaner than 1:2:4 including RCC man hle cober (1/9" dia 3"-1/2 thick) complete as per approved drawing and design by engineer in charge (pre-cast).	50	Nos	11,173.00	P.No	558,650

TOTAL Rs. 8,624,400

SH-II SEWERAGE LINE							
1	313/05	Excavation in all kinds of soil, murum, hard, average or soft including all lift and lead .	15284	cft	1840.9	%cft	281,365
2	313/05 +15upto 8 feet	9170	cft	2078.4	%cft	190,599
3	312/07	Providing R.C.C pipes and collars of class 'B' and fixing in trench i/c cutting ,fitting and jointing with maxphalt composition and cement mortar (1:1) and back filling the excaforvated material in trench i/c testing with water to a pressure head of 50 feet (15.24m) and cartage within 10 miles (16.09 km),for 12 inches (305mm) dia,pipe	1000	Rft	548.16	P.Rft	548,160

4	A/R	Providing circular manhole comprised of cylindrical and conical portions as per approved design and specifications complete with RCC 1:2:4 slab, 6 inches thick c.c. 1:3:6 Situ walls 9 inches thick with deduction of pipe holes CC 1:3:6 in foundation 6 inches thick and 1:2:4 CC in benching using sulphate resisting cement in all cc works including providing and fixing cast iron foot rest at every two feet of depth completed as per direction of engineer incharge but excluding the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	1000	cft	545.9	P.cft	545,900
5		Providing & laying R.C.C 1:2:4 slab cover 3" thick average (precast complete with M.S flat iron, M.S bars embedded in concrete) of any shape including the cost of reinforcement and welding etc. as per direction of Engineer Incharge.	20	cft	2274.73	P.cft	45,495
6		Making connection with the existing manhole including the cost of cutting holes in walls, making them good in cement concrete 1:2:4 and making the required channel etc.complete.	7	Nos	750.00	P.NO	5,250
					TOTAL Rs.		1,616,768



GOVERNMENT OF PAKISTAN
PAKISTAN PUBLIC WORKS DEPARTMENT
PAK. P.W.D. OFFICE BLOCK, 16-CANTT. STATION ROAD,
ADJACENT CANTT. POST OFFICE, SADDAR, KARACHI-75530
PH # 99332066

No. EE.CCD-VI/AB/NIT/4038

Karachi dated: 13th March 2024.

INVITATION TO BID

The Executive Engineer, Central Civil Division No. VI, Pak PWD, Karachi, invites sealed tenders, under Single Stage Two Envelope & on percentage rate basis for the work tabulated hereunder, from the Contractors/Firms registered with Income Tax, Sindh Revenue Board & having valid licence of Pakistan Engineering Council in appropriate category & field of specializations.

2. A complete set of Bidding Documents containing detailed terms and conditions may be purchased by an interested eligible bidder upon payment of a non-refundable fee as shown against each in cash.

3. Bidders will submit two sealed envelopes simultaneously, one containing the Technical Proposal and the other Financial Proposals, duly marked separately and enclosed together in an outer single envelope, in consonance with Rule-36(b) of PPRA 2004, so as to reach the undersigned. Technical proposals will be opened on the same day in the presence of bidders/representatives who choose to attend, at the same address. The time and schedule are narrated hereunder:

- | | | |
|------|--------------------------------------|----------------------------|
| i. | Issuance of Bidding documents up to: | 01-04-2024 (office Hours). |
| ii. | Casting / dropping of Bids up to: | 02-04-2024. 11:00 A.M. |
| iii. | Opening of Technical Bids on: | 02-04-2024. 11:30 A.M. |

4. In accordance with PPRA Rule-25; Bid Security i.e fixed amount as mentioned against each work is required, in shape of **CDR /Pay order/ Bank Draft/Bank Guarantee** by any schedule bank in favor of undersigned. The bidder will submit /attached original bid Security along with Technical Proposal; otherwise it will be treated NON-RESPONSIVE.

S. No.	Name of Schemes	Amount (Million)	Bid Security /Earnest Money	Tender Cost
1	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Arslan Homes, Shah Nawaz Bhutto Colony in UC-01, District Central North Karachi.	13.713	411,400	2,000
2	Providing and Fixing CC Tuff paver at Different streets of Sector-2 in UC-01, District Central North Karachi.	9.766	293,000	2,000
3	Providing and Fixing CC Tuff paver at Different streets of Sector-3 in UC-01, District Central North Karachi.	9.766	293,000	2,000
4	Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector 5A-1&2 in UC-02, District Central North Karachi.	13.713	411,400	2,000

5	<i>Providing and Fixing CC Tuff paver at Different streets of 5B1&2 in UC-02,District Central North Karachi.</i>	9.766	293,000	2,000
6	<i>Providing and Fixing CC Tuff paver at Different streets of 5A3&4 in UC-02,District Central North Karachi.</i>	9.766	293,000	2,000
7	<i>Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5B3 & 5C1 UC-03,District Central North Karachi.</i>	13.713	411,400	2,000
8	<i>Providing and Fixing CC Tuff paver at Different streets of Sector-5C2 in UC-03,District Central North Karachi.</i>	9.766	293,000	2,000
9	<i>Providing and Fixing CC Tuff paver at Different streets of Sector-4 in UC-03,District Central North Karachi.</i>	9.766	293,000	2,000
10	<i>Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector 5M & 5I in UC-04,District Central North Karachi.</i>	13.713	411,400	2,000
11	<i>Providing and Fixing CC Tuff paver at Different streets of Sector 5M in UC-04,District Central North Karachi.</i>	9.766	293,000	2,000
12	<i>Providing and Fixing CC Tuff paver at Different streets of Sector 5M & 5I in UC-04,District Central North Karachi.</i>	9.766	293,000	2,000
13	<i>Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5L & 5K in UC-08,District Central North Karachi.</i>	13.713	411,400	2,000
14	<i>Providing and Fixing CC Tuff paver at Different streets of Sector-5L in UC-08,District Central North Karachi.</i>	9.766	293,000	2,000
15	<i>Providing and Fixing CC Tuff paver at Different streets of Sector- 5K in UC-08,District Central North Karachi.</i>	9.766	293,000	2,000
16	<i>Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-11L,11I & 11K in UC-11,District Central North Karachi.</i>	13.713	411,400	2,000
17	<i>Providing and Fixing CC Tuff paver at Different streets of Sector-11L & 11I in UC-11,District Central North Karachi.</i>	9.766	293,000	2,000

18	<i>Providing and Fixing CC Tuff paver at Different streets of Sector-11I & 11K in UC-11,District Central North Karachi.</i>	9.766	293,000	2,000
19	<i>Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-5C3 & 5C4 in UC-12,District Central North Karachi.</i>	13.713	411,400	2,000
20	<i>Providing and Fixing CC Tuff paver at Different streets of Sector-11A in UC-12,District Central North Karachi.</i>	9.766	293,000	2,000
21	<i>Providing and Fixing CC Tuff paver at Different streets of Sector- 11B in UC-12,District Central North Karachi.</i>	9.766	293,000	2,000
22	<i>Providing and Fixing CC Tuff paver and RCC Sewerage 12" dia at Different streets of Sector-8 & 9 in UC-13,District Central North Karachi.</i>	13.713	411,400	2,000

Terms & Conditions:

6. No bidding document will be issued on the day of opening & no application will be entertained for issuance after cutoff date as mentioned at para 3(i), which will strictly be adhered to. The competent authority in accordance with PPRA Rules-33 of 2004 may reject all bids/proposals any time prior to the acceptance of a bid/proposal. Other terms and conditions as envisaged in the bidding documents will apply mutatis mutandis.

(IMRAN SHAMS)
Executive Engineer
Central Civil Div. No. VI,
Pak. P.W.D. Karachi.